




































GRADE OF CONCRETE FOR
COLUMNS/SW - M30 UP TO 4TH FLOOR

COLUMN FROM THIRD FLOOR LVL. TO FOURTH FLOOR LVL.	CONCRETE MIX – M30	● 8–25T ⊗ 16–20T 	● 4–25T ⊗ 16–20T 	● 20–20T ⊗ 4–16T 	● 4–25T ⊗ 16–20T 	● 8–16T ⊗ 22–12T 	● 16–16T ⊗ 4–12T 	● 8–25T ⊗ 16–20T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN FROM SECOND FLOOR LVL. TO THIRD FLOOR LVL.	CONCRETE MIX – M30	● 8–25T ⊗ 16–20T 	● 4–25T ⊗ 16–20T 	● 20–20T ⊗ 4–16T 	● 4–25T ⊗ 16–20T 	● 8–16T ⊗ 22–12T 	● 16–16T ⊗ 4–12T 	● 8–25T ⊗ 16–20T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN FROM FIRST FLOOR LVL. TO SECOND FLOOR LVL.	CONCRETE MIX – M30	● 8–25T ⊗ 16–20T 	● 4–25T ⊗ 16–20T 	● 20–20T ⊗ 4–16T 	● 4–25T ⊗ 16–20T 	● 12–16T ⊗ 18–12T 	● 8–20T ⊗ 12–16T 	● 8–25T ⊗ 16–20T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN FROM GROUND FLOOR LVL. TO FIRST FLOOR LVL.	CONCRETE MIX – M30	● 18–25T ⊗ 8–20T 	● 14–25T ⊗ 8–20T 	● 6–25T ⊗ 20–20T 	● 14–25T ⊗ 8–20T 	● 6–20T ⊗ 26–16T 	● 6–25T ⊗ 16–20T 	● 18–25T ⊗ 8–20T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN FROM FOUNDATION LVL. TO GROUND FLOOR LVL.	CONCRETE MIX – M30	● 18–25T ⊗ 8–20T 	● 14–25T ⊗ 8–20T 	● 6–25T ⊗ 20–20T 	● 14–25T ⊗ 8–20T 	● 6–20T ⊗ 26–16T 	● 6–25T ⊗ 16–20T 	● 18–25T ⊗ 8–20T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN		TA–C6, TA–C30	TA–C7, TA–C31	TA–C8, TA–C32	TA–C10, TA–C11, TA–C26, TA–C27	TA–C13	TA–C14, TA–C24	TA–C9, TA–C25

PLACEMENT OF
FIRST STIRRUP FROM
THE FACE OF COLUMN/SW
NOT MORE THAN "50MM" IN ANY CASE

COLUMN/SW STIRRUPS MUST BE
THROUGH AT THE BEAM–COULMN/SW
JOINTS/JUNCTIONS AND SPACING MUST
BE AS PER DETAILS

PLACEMENT OF
FIRST STIRRUP FROM
THE FACE OF COLUMN/SW
NOT MORE THAN "50MM" IN ANY CASE

COLUMN R/F. STOPS ("L" BENT)

AS PER
DETAILS

AS PER
DETAILS

COLUMN NEW R/F. START

TYPICAL DETAILS FOR
STIRRUPS AT REDUCTION OF
COLUMNS/SHEAR WALLS
(ONE SIDE)

PLACEMENT OF
FIRST STIRRUP FROM
THE FACE OF COLUMN/SW
NOT MORE THAN "50MM" IN ANY CASE


PLACEMENT OF
FIRST STIRRUP FROM
THE FACE OF COLUMN/SW
NOT MORE THAN "50MM" IN ANY CASE

COLUMN/SW STIRRUPS MUST BE THROUGH
AT THE BEAM–COULMN/SW JOINTS AND
SPACING MUST BE AS PER DETAILS


AS PER
DETAILS

AS PER
DETAILS

TYPICAL DETAILS FOR
STIRRUPS PLACEMENTS FOR
BEAMS AND COLUMNS




FOR 135° HOOK



FOR 180° HOOK

TYPICAL DETAIL OF
HOOKS




TYPICAL ZONING FOR
DUCTILE DETAILS
OF COLUMNS / SW

GENERAL NOTES :-

- ALL DIMENSIONS ARE IN MM.
- FOR ALL NOTES, REFER OUR DRG NO: S0–01 TO S0–09.
- CEMENT SHALL BE OPC 43 GRADE OR HIGHER / AS PER TENDER SPECIFICATIONS & PORTABLE WATER SHOULD BE USE.
- SUPERVISION SHALL NOT BE OUR RESPONSIBILITY.
- TO TAKE OUT THE CUBE AND MATERIAL TESTING SHALL BE CONTRACTOR/ BUILDER/CLIENTS RESPONSIBILITY.
- LOAD TESTING OF STRUCTURE SHALL NOT BE OUR RESPONSIBILITY.
- ALL DIMENSIONS ARE TO BE READ AND NOT TO BE MEASURED
- T OR # INDICATE STEEL FE 500D GRADE TMT BARS.
- ALL CONC.MIX. M:30 UNLESS OTHERWISE SPECIFIED.
- LO.LD = DEVELOPMENT LENGTH : 50 X φ; WHERE, φ = DIA. OF BAR.
- ALL BRICK WORK SHALL BE IN C.M. (1:6)
- STRUCTURAL LAY OUT SHOULD BE REFER ONLY FOR STRUCTURAL DETAILING.
- PLEASE REFER ARCHITECTURAL DWG FOR LVLS. & SETTINGS OUT CENTERLINE DIMENSIONS. THE CENTERLINE PUT IN THIS STRUCTURAL FOUNDATION LAYOUT IS SIMPLY INDICATIVE OF LOCATION AND AS APPROVED BY ARCHITECT.
- PLEASE REFER ARCH. DWG. FOR FINAL LAY OUT.
- CONTRACTOR SHOULD INFORM ARCHITECT/STRUCTURAL CONSULTANT IN CASE OF ANY CHANGE IN EXISTING CONDITION FOUND, IMMEDIATELY
- THIS DRG. SHOULD BE READ ALONG WITH ARCHITECTURAL DRGS.AND ANY CHANGES/DEVIATION FOUND SHOULD BE IMMEDIATELY BROUGHT TO NOTICE OF ARCHITECT & STR. ENGINEER
- THIS DWG.SHOULD BE READ ALONG WITH RELEVANT DETAILS
- MIX DESIGN SHOULD BE GOT APPROVED PRIOR TO EXECUTION OF WORK
- ALL STEEL (TOP/BOTTOM) OF DIFFERENT ZONE SHALL BE LAPPED IN ADDITION WHERE THE ZONE TERMINATES; BY LENGTH EQUAL TO THE DEVELOPMENT LENGTH OF HIGHER DIA BAR.

KEY PLAN



GRADE OF CONCRETE

ALL STRUCTURAL
ELEMENTS

M30

CONCRETE COVER

FOOTINGS /RAFT	50MM
COLUMNS/SW	40MM
BEAMS	30MM
SLABS	25MM
PARDI WALLS	30MM



1	29-12-21	GOOD FOR CONSTRUCTION		
---	----------	-----------------------	--	--

NO.	DATE	REVISION / REMARK	BY	DR	CH
-----	------	-------------------	----	----	----

JOB TITLE / DEVELOPER

TURQUOISE-GRANDEUR
RATANA DEVELOPERS

DRAWING TITLE

COLUMN SCHEDULE DETAIL - TOWER-A

JOB NO 2111		DATE 16/04/2021		DRG. NO. S5-TA-04		REVISION R0	
SCALE 1 : 100	SHEET SIZE A1/A2/A3		DRAWN AKSHAY		DESIGN KUNJ		CHECKED BHAVIK PATEL

ARCHITECTS



HM ARCHITECTS
e:contact@hmarchitects.in

STRUCTURAL CONSULTANT



email:blueskyzengineers@gmail.com