




























GRADE OF CONCRETE FOR
COLUMNS/SW - M35 UP TO 4TH FLOOR


COLUMN FROM THIRD FLOOR LVL. TO FOURTH FLOOR LVL.	CONCRETE MIX – M30	● 20–16T ⊗ 8–12T 	● 20–20T ⊗ 4–16T 	● 20–16T ⊗ 4–12T 	● 24–12T 	● 8–20T ⊗ 12–16T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN FROM SECOND FLOOR LVL. TO THIRD FLOOR LVL.	CONCRETE MIX – M30	● 20–16T ⊗ 8–12T 	● 20–20T ⊗ 4–16T 	● 20–16T ⊗ 4–12T 	● 24–12T 	● 8–20T ⊗ 12–16T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN FROM FIRST FLOOR LVL. TO SECOND FLOOR LVL.	CONCRETE MIX – M30	● 8–20T ⊗ 20–16T 	● 24–20T 	● 20–16T ⊗ 4–12T 	● 24–12T 	● 8–20T ⊗ 12–16T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN FROM GROUND FLOOR LVL. TO FIRST FLOOR LVL.	CONCRETE MIX – M30	● 30–20T 	● 6–25T ⊗ 20–20T 	● 6–20T ⊗ 20–16T 	● 26–12T 	● 18–20T ⊗ 4–16T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN FROM FOUNDATION LVL. TO GROUND FLOOR LVL.	CONCRETE MIX – M30	● 30–20T 	● 6–25T ⊗ 20–20T 	● 6–20T ⊗ 20–16T 	● 26–12T 	● 18–20T ⊗ 4–16T 
		COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)	COL. RING/LINK 8T–100 C/C (8 NOS.–Z1) 8T–100 C/C (AT MID–Z2)
COLUMN		TA–C15, TA–C19	TA–C12, TA–C28	TA–C16, TA–C20	TA–C18, TA–C22	TA–C17, TA–C21




TYPICAL DETAILS FOR
STIRRUPS AT REDUCTION OF
COLUMNS/SHEAR WALLS
(ONE SIDE)




TYPICAL DETAILS FOR
STIRRUPS PLACEMENTS FOR
BEAMS AND COLUMNS



TYPICAL ZONING FOR
DUCTILE DETAILS
OF COLUMNS / SW



FOR 135° HOOK




FOR 180° HOOK
TYPICAL DETAIL OF
HOOKS

GENERAL NOTES :-

- ALL DIMENSIONS ARE IN MM.
- FOR ALL NOTES, REFER OUR DRG NO: S0–01 TO S0–09.
- CEMENT SHALL BE OPC 43 GRADE OR HIGHER / AS PER TENDER SPECIFICATIONS & PORTABLE WATER SHOULD BE USE.
- SUPERVISION SHALL NOT BE OUR RESPONSIBILITY.
- TO TAKE OUT THE CUBE AND MATERIAL TESTING SHALL BE CONTRACTOR/ BUILDER/CLIENTS RESPONSIBILITY.
- LOAD TESTING OF STRUCTURE SHALL NOT BE OUR RESPONSIBILITY.
- ALL DIMENSIONS ARE TO BE READ AND NOT TO BE MEASURED
- T OR # INDICATE STEEL FE 500D GRADE TMT BARS.
- ALL CONC.MIX. M:30 UNLESS OTHERWISE SPECIFIED.
- LD = DEVELOPMENT LENGTH : 50 X φ; WHERE, φ = DIA. OF BAR.
- ALL BRICK WORK SHALL BE IN C.M. (1:6)
- STRUCTURAL LAY OUT SHOULD BE REFER ONLY FOR STRUCTURAL DETAILING.
- PLEASE REFER ARCHITECTURAL DWG FOR LVLS. & SETTINGS OUT CENTERLINE DIMENSIONS. THE CENTERLINE PUT IN THIS STRUCTURAL FOUNDATION LAYOUT IS SIMPLY INDICATIVE OF LOCATION AND AS APPROVED BY ARCHITECT.
- PLEASE REFER ARCH. DWG. FOR FINAL LAY OUT.
- CONTRACTOR SHOULD INFORM ARCHITECT/STRUCTURAL CONSULTANT IN CASE OF ANY CHANGE IN EXISTING CONDITION FOUND, IMMEDIATELY
- THIS DRG. SHOULD BE READ ALONG WITH ARCHITECTURAL DRGS.AND ANY CHANGES/DEVIATION FOUND SHOULD BE IMMEDIATELY BROUGHT TO NOTICE OF ARCHITECT & STR. ENGINEER
- THIS DWG.SHOULD BE READ ALONG WITH RELEVANT DETAILS
- MIX DESIGN SHOULD BE GOT APPROVED PRIOR TO EXECUTION OF WORK
- ALL STEEL (TOP/BOTTOM) OF DIFFERENT ZONE SHALL BE LAPPED IN ADDITION WHERE THE ZONE TERMINATES; BY LENGTH EQUAL TO THE DEVELOPMENT LENGTH OF HIGHER DIA BAR.

KEY PLAN



GRADE OF CONCRETE

ALL STRUCTURAL ELEMENTS	M30
-------------------------	-----

CONCRETE COVER

FOOTINGS /RAFT	50MM
COLUMNS/SW	40MM
BEAMS	30MM
SLABS	25MM
PARDI WALLS	30MM

1	29-12-21	GOOD FOR CONSTRUCTION			
NO.	DATE	REVISION / REMARK	BY	DR	CH

JOB TITLE / DEVELOPER

TURQUOISE-GRANDEUR
RATANA DEVELOPERS

DRAWING TITLE

COLUMN SCHEDULE DETAIL - TOWER-A


JOB NO 2111		DATE 16/04/2021		DRG. NO. S5-TA-07		REVISION R0			
SCALE 1 : 100		SHEET SIZE A1/A2/A3		DRAWN AKSHAY		DESIGN KUNJ		CHECKED BHAVIK PATEL	

ARCHITECTS



HM ARCHITECTS
e:contact@hmarchitects.in

STRUCTURAL CONSULTANT



email:blueskyzengineers@gmail.com